SAFE QLD PTY LTD
ABN 51 130 129 270
66 BAY ST, CLEVELAND Q 4163
P: 07 3286 6310 | E: matt@safeqld.com.au
www.safeqld.com.au

***Ref: 6136***

**Thursday, March 27, 2025**

**RESPONSE TO REQUEST FOR PROPOSED FIRE SERVICES**

**ABRONIA APARTMENTS – 41 Skyview Ave, Rochedale.**

Thank you for the opportunity to submit a proposal for the above-named project.

**SYSTEMS OFFERED – DRY FIRE**

- Automatic Fire Detection and Emergency warning system.(FDCIE/EWCIE/FFCP)
- Interface with buildings combined hydrant/sprinkler system (AS2118).
- Interface with Mechanical plant basements

**BASIS OF PROPOSAL – DESIGN & CONSTRUCT – DRY FIRE SERVICES.**

Our proposal has been prepared in general accordance with the following documentation.

- Relevant Australia Standards: NCC 2022 V1, AS3000 AS1668 and AS1670.1-2018
- Fire Drawings: 2024299; FA000-2, fa100-1, FA101-2, FA102-2, FA103-1, FA200-2, FA201-2, FA202-2, FA203-2, FA204-2, FA205-1,FA300-2
- WBFE884-001-2022 Rev 002 20-12-24
- Design and Construct Fire Alarm Services Specification – Issue 1 - March 04th 2025

**Proposal Price:**

| | |
|---|---|
| **Fire Alarm System Price:**<br><br>**Building A: $60,260.00**<br>**Building B: $95,060.00** | **$155,320.00** |
| **GST:** | **$ 15,532.00** |
| **Total Price: Including GST** | **$170,852.00** |
| ***Our Fixed Price will remain valid for 60 days from the date of submission.*** | |

**SCOPE OF WORKS – Building A & B**

- Main FDCIE in Building B and Sub FDCIE in Building A.
- Allowance for capacity to link to future stages in the first and subsequent stages.
- Fire Control Centre in each building - Networked addressable fire detection control and indicator panel with combined emergency warning system. Including all fire fan controls. FDCIE/EWCIE/FFCP
- Interface with building combined hydrant/sprinkler system, fire pumps, monitoring valves, control valves, DBA, booster cabinet IV and pressure switch for a complete system.
- Interface with basement mechanical plant, smoke exhaust fans, supply air fans and jet fans. Including duct probes, onboard jet fan smoke detectors and circulation space smoke detectors in accordance with the FEB & AS1670 & AS1668.

SAFE QLD PTY LTD
ABN 51 130 129 270
66 BAY ST, CLEVELAND Q 4163
P: 07 3286 6310 | E: matt@safeqld.com.au
www.safeqld.com.au

- Allowance for FDCIE to initiate a signal to the respective mechanical services switchboards for fire mode shutdown of air handling systems. Allowance to liaise closely with the mechanical services contractor to ensure all control functions operate in accordance with the requirements of AS 1668, AS 2118, AS 1670 and the specification.
- Addressable smoke detectors in all public corridors and internal public spaces in accordance with NCC and AS1670.1.
- Allowance for MASD for protection of the top of lift shafts as per drawings.
- Evacuation speakers in all bedrooms and horn speakers throughout basement in accordance with NCC and AS1670.1.
- Fire Alarm red strobe to building entry and booster location to indicate when building is in alarm.
- Fire signal to fire doors, auto doors and gates to auto unlock in case of fire where used as a path of escape.
- Fire signal to Electric Vehicle charging power shutdown control circuit in the fire control room
- Fire signal to gas shutoff solenoid on activation of fire alarm.

**GENERAL**

- Fire cable, conduit in slabs, fixings and sundries.
- Allowance to fire rate all required fire system penetrations and certification.
- Provision of a fire alarm signal to the security/access control system for release of specified doors & electric locks.
- Commissioning of fire system and interface performance testing with other associated trades.
- Shop and as-Installed drawings.
- Commissioning documentation (Form 12) baseline data and installers statements.
- QFES inspection
- Provision of alarm signaling equipment (ASE) in the FIP. Include dual 4G connection facility.
- FDCIE block diagrams
- Operations & Maintenance Manuals
- 12 months warranty
- 12 Months maintenance compliant with AS1851 for the DLP

**CLARIFICATIONS/EXCLUSIONS**

1. All work will be carried out during normal working hours 6:30am to 3:30pm Monday to Saturday excluding public and award prescribed holidays or as required to maintain sequencing the works program.
2. We have made no allowances in this quote for installing electronic security systems door holding devices, tactical evacuation plans, fire blankets, sprinkler systems, extinguishers, sliding fire doors interface, Magnetic door holders, MCPs, emergency lighting or fire hydrants/hose reels. If required, we can provide additional quotations on request.
3. No allowance for brigade connection and ASE. Local alarm only
4. No allowance for FFCP due to no mechanical carpark ventilation required.

We trust that this proposal meets with your approval and await your further advice. Should you require any further information, advice or clarification regarding this quotation, please do not hesitate to contact me.

SAFE QLD PTY LTD
ABN 51 130 129 270
66 BAY ST, CLEVELAND Q 4163
P: 07 3286 6310 | E: matt@safeqld.com.au
www.safeqld.com.au

**Yours Faithfully,**

Matt Anderson

T: 07 3286 6310 | M: 0400 049 585 |E: matt@safeqld.com.au