SAFE QLD PTY LTD
ABN 51 130 129 270
66 BAY ST, CLEVELAND Q 4163
P: 07 3286 6310 | E: matt@safeqld.com.au
www.safeqld.com.au

Ref: 6172

Thursday, May 01, 2025

RESPONSE TO REQUEST FOR PROPOSED FIRE SERVICES

7 Zupp Drive, Ormeau QLD 4208

Thank you for the opportunity to submit a proposal for the above-named project.

SYSTEMS OFFERED – DRY FIRE

- Automatic Fire Detection and Emergency warning system.
- Interface with Sprinkler system – Basement levels
- Interface with Mechanical plant

BASIS OF PROPOSAL – DESIGN & CONSTRUCT – DRY FIRE PROTECTION.

Our proposal has been prepared in general accordance with the following documentation.

- Relevant Standards: NCC 2022 V1, AS3000, AS1851 and AS1670.1
- Architectural Drawings: W035-07-WD
- B10224100-FEB-01
- B10224100-Proposed Alternative Solutions

Proposal Price:

Fire Alarm Price: Excluding GST	**$113,930.00**
GST:	**$ 11,393.00**
Total Price: Including GST	**$125,323.00**
Our Fixed Price will remain valid for 60 days from the date of submission.	

Scope of Works – Fire Detection and Emergency Warning System

- Supply and installation of a new addressable fire detection control and indicator panel with integrated emergency warning and intercommunication system (FDCIE/EWCIE/FFCP), including fire fan control panel housed within the FDCIE enclosure.
- Provision for interfacing with the building's sprinkler system, including pumps, isolation valves, and pressure switches. Connections will be made to sprinkler control valves and flow switches on each level.
- Installation of addressable smoke and heat detectors in all public areas in compliance with the National Construction Code (NCC) and AS1670.1.
- Provision for smoke detectors associated with jet fans (supplied by the mechanical contractor), with one fan control point per level as per Fire Engineering Brief (FEB) requirements.

SAFE QLD PTY LTD
ABN 51 130 129 270
66 BAY ST, CLEVELAND Q 4163
P: 07 3286 6310 | E: matt@safeqld.com.au
www.safeqld.com.au

- Installation of evacuation speakers throughout all areas and horn speakers in basement levels, in accordance with NCC and AS1670.1 standards.
- Installation of an external red strobe at the designated building entry point for QFES (Queensland Fire and Emergency Services) access.
- Supply and installation of all required fire-rated cabling, conduit works within slabs, fixings, and associated sundry items.
- Fire rating of all required penetrations for the fire system, including registration and provision of Form 12 certification.
- Full commissioning of the fire system and interface performance testing in coordination with all relevant trades.
- Preparation and submission of detailed shop drawings and as-installed documentation.
- Provision of commissioning documentation, including Form 15, Form 12, baseline data, and installer statements.
- Coordination of QFES inspection and submission of OM54 application forms for ASE installation.
- Preparation and supply of FDCIE block diagram.
- Delivery of complete Operations and Maintenance (O&M) manuals.
- 12-month system warranty.
- On-site client training session (30-minute allowance).
- 12-month maintenance period in accordance with AS1851, covering the Defects Liability Period (DLP).

CLARIFICATIONS/EXCLUSIONS

1. All work will be carried out during normal working hours 6:30am to 3:30pm Monday to Saturday excluding public and award prescribed holidays or as required to maintain sequencing the works program.
2. We have made no allowances in this quote for installing electronic security systems door holding devices, tactical evacuation plans, fire blankets, sprinkler systems, portable appliances, sliding fire doors, Magnetic door holders, MCPs, EV Charger fire trips or fire hydrants/hose reels. If required, we can provide additional quotations on request.
3. No allowance for brigade fees & rentals

We trust that this proposal meets with your approval and await your further advice. Should you require any further information, advice or clarification regarding this quotation, please do not hesitate to contact me.

Yours Faithfully,

SAFE QLD PTY LTD
ABN 51 130 129 270
66 BAY ST, CLEVELAND Q 4163
P: 07 3286 6310 | E: matt@safeqld.com.au
www.safeqld.com.au

Matt Anderson

T: 07 3286 6310 | M: 0400 049 585 |E: matt@safeqld.com.au